





## **CSS DRYWALL AND FRAMING DATABASE**

The Construction Support Services
Drywall & Framing database has
over 1500 items of work for General
Conditions, Structural Light Gauge
Framing, Wood Framing, Insulation,
Drywall, Ceilings and Painting. The
phase structure of the database is
arranged in the 2015 divisions of the
CSI Master Format.

This database is complete with labor productivity, material unit pricing and Subcontractor pricing which can be modified by the end user with their specific historical data.

The database includes extensive assembly help files with sample details and photos for every

assembly accessible from both estimating and eTakeoff.

eTakeoff traces and Bridge mappings are included with the database.

## **Database Specifications**

Over 70 Phases Over 1,500 Items Over 60 Assemblies

<b>Division</b>	# of Assemblies
<b>General Conditions</b>	3 2
Metals	5
Wood & Plastics	25
Thermal & Moisture	e 7
Openings	6
Finishes	19
Total	64

Interior It Co. Wells			
Interior Lt.Ga. Walls			
	Quantity	1.000	
	Length	50.000	If
	Height Wall '	10.000	ft
	Stud Spacing "	16.000	in
	tga Stud Width	3.500	in
16 = 16ga	Stud Gauge	22,000	
	ner Bead Regd.?	Yes	
	Outside Corners	1.000	ea
	dging this Wall	1.000	
		1.000	
	ndow Openings		Ed
	Bracing Reqd.?	No	
	s & Pins Reqd.?	Yes	
Shots	& Pin Spacing	12.000	in
Gyp	p. Board Reqd.?	Yes	
No_Sides Sheetrock		2.000	ea
Hei	ght Sheetrock '	10.000	ft
No_Lay	ers Rock Side 1	1.000	ea
-	ard Code Side 1	5.000	
	ers Rock Side 2		ea
	lient Channels?	No	
I/CSI		140	
	# Layers Rock		ea
	heathing Reqd?	No	
Ba	tt Insul. Reqd.?	No	

06-056		Misc. Blocking - Length								
	06-11-05	2x8 RL #2 SPF	35.79 If	-		-	-	-	2.35 /bf	112
	06-11-05	Labor - Blocking/Nailers	35.79 If	0.040 hr/lf	1	28.28 /hr	1.13 /lf	40	-	
09-005		Exterior Lt.Ga. Walls								
	09-22-16	Wall Framing Labor / If	242.57 If	0.140 hr/lf	34	28.00 /hr	3.92 /lf	951	-	
	09-22-16	18 Ga. 6" Stud	1,839.30 lf	-		-	-	-	3.62 /lf	6,655
	09-22-16	18 Ga. 6" Track	485.15 lf	-		-	-	-	3.07 /lf	1,488
	09-22-16	1-1/4" Metal Corner Bead	40.00 lf	0.011 hr/lf	0	28.00 /hr	0.31 /lf	12	4.92 /pc	25
	09-22-16	1-1/2" 16ga Bridging	242.57 If	0.039 hr/lf	9	28.06 /hr	1.08 /lf	262	2.07 /lf	502
	09-22-16	Door/Window Opening Labor	11.00 ea	1.000 hr/ea	11	28.05 /hr	28.05 /ea	309	-	-
	09-22-16	Shots & Pins	243.00 ea	-		-	-	-	1.07 /ea	261
	09-21-16	5/8" Sheetrock(F.R)	2,425.73 sf	0.013 hr/sf	30	28.06 /hr	0.35 /sf	851	0.52 /sf	1,261
	09-22-16	Screws	2,425.73 sf	-		-	-	-	0.04 /sf	87
	06-16-05	5/8" Dens-Glass LxH	2,425.73 sf	0.030 hr/sf	73	28.00 /hr	0.84 /sf	2,038	80.33 /st	6,089
	07-27-05	House Wrap Air Barrier	2,668.30 sf	0.006 hr/sf	15	28.00 /hr	0.15 /sf	411	0.20 /sf	536
	07-21-16	Knauf Foil-Faced 6.25" R19 Batts	2,425.73 sf	0.024 hr/sf	58	28.00 /hr	0.67 /sf	1,630	0.98 /sf	2,377

## Example of the Assembly Help files attached to each assembly



